BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/02/2020-21 Date: 10.06.2020

Indet No: BBMP/2020-21/RD/WORK_INDENT42807

SCHEDULE -B

Name of Work: Emergency works in Jalahalli surroundings area in ward no 16 jalahalli

Sl. No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	511.20	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	115.00	Rupees One Hundred Fifteen Only
2	265.20	KSRB 2-1 : Earthwork in surface excavation for levelling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications.	Cum	275.00	Rupees Two Hundred Seventy Five Only
3	76.68	KSRB 4-1.7 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	5897.00	Rupees Five Thousand Eight Hundred Ninety Seven Only
4	681.60	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm	Sqm	1074.00	Rupees One Thousand Seventy Four Only
5	340.80	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. - do - 10 cms thick	Cum	1013.00	Rupees One Thousand Thirteen Only
6	1817.60	KSRB 5-9 : Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded)	Rmtr	62.73	Rupees Sixty Two And Paise Seventy Three Only
7	852.00	KSRB 5-8.1 : Providing one line dressing to granite stone slab / granite stone masonry as per specifications.	sqm	996.00	Rupees Nine Hundred Ninety Six Only
8	235.00	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per pecifications.	Sqm	99.71	Rupees Ninety Nine And Paise Seventy One Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor